



3" LAYER OF WOOD MULCH
KEEP 3" AWAY FROM TREE
CROWN. NOT REQUIRED IN
LAWN AREAS.

3" HIGH SOIL WATERING
BASIN. NOT REQUIRED IN
LAWN AREAS.

FINISHED GRADE

12" DIA. X 10' DEEP AUGERED
HOLE. BACKFILL WITH EXCAVATED
MATERIAL AND JET. ALLOW SOIL
TO SETTLE FOR FOUR DAYS PRIOR
TO PLANTING. PROVIDE AUGERED
HOLE ONLY IF SPECIFIED.

NOTE:

1. FOR 36" BOX TREES. STAKE WITH TWO 2" X 12' LONG SCHEDULE 40 GALVANIZED STEEL PIPES. PAINTED WITH TWO COATS OF DARK GREEN PAINT. TIE TREE WITH A METAL TWIST BRACE BOLTED TO THE STAKES OR OTHER APPROVED TREE TIE AS SPECIFIED.

END OF STAKE SHALL NOT
EXTEND INTO TREE CANOPY.
CUT AS NECESSARY

RUBBER CINCH TREE TIE. NAIL
THROUGH KNOT. FOUR (4)
PER TREE

2" DIA. PRESSURE-TREATED LODGE
POLE PINE TREE STAKE. TWO (2)
PER TREE

PLACE ROOTBALL 1" ABOVE
FINISHED GRADE. PROVIDE
POSITIVE DRAINAGE AWAY FROM
CROWN.

PLANTING PIT SHALL BE 2X
THE DIAMETER OF THE ROOTBALL
SCARIFY SIDES/BOTTOM AND
BACKFILL WITH NATIVE SOIL

ROOT BALL

FERTILIZER TABLET OR PACKET
TYP. SEE SPECIFICATIONS

UNDISTURBED SOIL

TREE STAKES SHALL BE
INSTALLED A MINIMUM OF
6" INTO UNDISTURBED SOIL

[Handwritten Signature]
DIRECTOR

COUNTY OF SACRAMENTO
PUBLIC WORKS AGENCY
DEPARTMENT OF TRANSPORTATION



TREE PLANTING

SCALE: NONE
DATE: 11/2000

DRAWN BY: GMM
CHECKED BY: GMM

SHEET:
L-1